BRUHATH BANGALORE MAHANAGARA PALIKE

Dasarahalli Zone

NAME OF WORK: Drilling of Borewells and Providing Pump Motor & Electrification in Ward No 14, Bagalagunte

Job Code-014-19-000052						Est.Cost	40.00	Lakhs
Sl	Description Of Item	Unit	No	L	B	D	Qty		Amount
1	Geophysical survey geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the hand pumps, MWS or PWSS by vertical electrical sounding by adopting venner or schlumbergers's method including recconnaisance suevey of geological formation Geophysical investigation of existing ground Water in the vicinity. its quality , quality & acceptabality of the users indicating the location of the site recommendeddepth of casing pipe required to seal the tope unconsolidated formation including an extra depth 1.0 metre in consolidated formation for aquire proposed to be tapped propable yield and other information required including transportation of instrument and accessories to work site, engating technical personal and labour etc.,PRE- Bangalore Circle-2014-15 Page No-47 & 48 , Item No-9.4								
		Each	4				4.00	1938.46	7754.00
2	Sinking of Borewell of 165 mm clear using fast hydraulic rig of capacity 250 PSIG & above 900 CMF & abpve in al strata including over burden upto 22 m fixing of casing pipes, collars and cap with necessary cutting and threading including transporation of rig and surpporting vehicles, screws charges and cost of consumable including yield testing at the final depth with a minimum working of compressor for one hour all as specified.,PRE- Bangalore Circle-2014-15, Page No-46, Item No-9.1.1 to 9.1.7								
a	Sheshadri Layout							Per/Rmtr	
	0.00 to 50.00 mtrs	Rmtr	1	50.00			50.00	315.18	15759.00
	50mtr to 100.00 mtr		1	50.00			50.00	412.60	20630.00
	100.00 to 150.00 mtr		1	50.00			50.00	458.35	22918.00
	150.00 to 200.00 mtr		1	50.00			50.00	484.10	24205.00
	200.00 to 250.00 mtr		1	50.00			50.00	560.32	28016.00
	250.00 to 300.00 mtr		1	50.00			50.00	600.49	30025.00
	300.00 to 350.00 mtr		1	50.00			50.00	640.60	32030.00
	350.00 to 365 Mtr		1	15.00			15.00	677.74	10166.00
b	Siddeshwara Layout								
	0.00 to 50.00 mtrs	Rmtr	1	50.00			50.00	315.18	15759.00
	50mtr to 100.00 mtr		1	50.00			50.00	412.60	20630.00
	100.00 to 150.00 mtr		1	50.00			50.00	458.35	22918.00
	150.00 to 200.00 mtr		1	50.00			50.00	484.10	24205.00
	200.00 to 250.00 mtr		1	50.00			50.00	560.32	28016.00
	250.00 to 300.00 mtr		1	50.00			50.00	600.49	30025.00
	300.00 to 350.00 mtr		1	50.00			50.00	640.60	32030.00
	350.00 to 358 Mtr		1	8.00			8.00	677.74	5422.00
c	Manjunatha Nagara								
	0.00 to 50.00 mtrs	Rmtr	1	50.00			50.00	315.18	15759.00
	50mtr to 100.00 mtr		1	50.00			50.00	412.60	20630.00
	100.00 to 150.00 mtr		1	50.00			50.00	458.35	22918.00
	150.00 to 200.00 mtr		1	50.00			50.00	484.10	24205.00
	200.00 to 250.00 mtr		1	50.00			50.00	560.32	28016.00

Scanned by CamScanner

	250.00 to 300.00 mtr		1	50.00			50.00	600.49	30025.00
	300.00 to 350.00 mtr		1	50.00			50.00	640.60	32030.00
	350.00 to 360 Mtr		1	10.00			10.00	677.74	6777.00
d	Soundarya Layout								
	0.00 to 50.00 mtrs	Rmtr	1	50.00			50.00	315.18	15759.00
	50mtr to 100.00 mtr		1	50.00			50.00	412.60	20630.00
	100.00 to 150.00 mtr		1	50.00			50.00	458.35	22918.00
	150.00 to 200.00 mtr		1	50.00			50.00	484.10	24205.00
	200.00 to 250.00 mtr		1	50.00			50.00	560.32	28016.00
	250.00 to 300.00 mtr		1	50.00			50.00	600.49	30025.00
	300.00 to 350.00 mtr		1	50.00			50.00	640.60	32030.00
	350.00 to 365 Mtr		1	15.00			15.00	677.74	10166.00
3	Supply of ISI Mark 175mm Nominal bore ,plain end steel Casing pipe grade of steel Fee 410 of wall thickness 5.4 mm thick confirming to IS 1387/1933 and manufactured by basic open hearth electric or basic oxygen process in random lenth of 5 to 7mtrs. Both ends threaded Confirming to IS 554/1985, One end fixed with a Socket Confirming to IS 4270:2001 and the other end with Screwed pipes . All pipes shall be reasonably free from defectes. The tube shall be reasonably straight should be with ISI marking, weighing 25.10kg/mtr. (Inclusive of all taxes) (PRED,2012-13 Page No.iii, item No-84)								
	Sheshadri Layout		1	30			30.00	1325.00	39750.00
	Siddeshwara Layout		1	33			33.00	1325.00	43725.00
	Manjunatha Nagara		1	32			32.00	1325.00	42400.00
	Soundarya Layout		1	35			35.00	1325.00	46375.00
4	Providing and Fixing 250mm dia PVC pipe and as per Specification and Direction (BWSSB SR 13-14, P.No.53, IT.No01 of Sl No.11								
		Each	4	18			72.00	1133.00	81576.00
5	Providing 175 mm dia MS Collar (RDED SR page ii, item86)								
		Each	4	26			104.00		
							104.00	150.00	15600.00
6	Providing 175 mm dia MS Cap(as per RDED SR page ii, item-85)								
		Each	4	1			4.00	100.00	400.00
7	Supply and delivery at site brand new submersible pumpset suitable for borewell of 165mm dia and having the declared duty conditions as detailed below and satisfying performance Characteristics for pump and motor as declared by the bureau of indian stand. the pumpset should conform to IS : 8034-1989 (With all its latest amendments) and Should bear ISI Certification mark IS : 8034-1989 Sub mercible pumpset 20HP 40 stage Texmo/Taro or equalents Brands (KPWD SR 2018-19 Page No: XLII Item No.56)								
	Sheshadri Layout	No	1	1			1.00	85197.50	85198.00
	Siddeshwara Layout		1	1			1.00	85197.50	85198.00
	Manjunatha Nagara		1	1			1.00	85197.50	85198.00
	Soundarya Layout		1	1			1.00	85197.50	85198.00
	Basic Rate	80375.00							
	Area Weightage 6%	4822.50							
	Total	85197.50							
8	Providing and fixing of 50mm G.I pipe 'B' class heavy duty for erection of submersible pumpset galvanised tube 50mm supply ad delivary of cause heavy duty as per IS/239/1990 (P No.XLVII, SL.No 01) PWD SR 2018-19								
	Sheshadri Layout	Mtrs	1	270			270.00	439.90	118773.00
	Siddeshwara Layout		1	250			250.00	439.90	109975.00

Scanned by CamScanner

	Manjunatha Nagara		1	265			265.00	439.90	116574.00
	Soundarya Layout		1	255			255.00	439.90	112175.00
	Basic Rate	415.00							
	Area Weightage 6%	24.90							
	Total	439.90							
9	Supplying and Drawing 3 core Flat PVC Shalted **Submersible Pump** Cable Manufactured with Electrolytic Grade Copper with Flexible copper conductor to table 3 class 5 of IS 8130-1984 and Virgen PVC insulation and Sheeated Suitable for working Voltage Upto 1100 Volts BWSSB SR 2014-15, P- 535, I. 30Page no:12 sl no: 2.10.4								
		Mtrs	3	550.00			1650.00		
							1650.00	164.29	271079.00
10	Supplying and delivery at site brand new star / Essen / Lotus / Sun shines / Adharsh / GK Controls best indigenous make combined energy meter cum control panel board unit of size 1200x600x350mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for opration on 3ph, 50 hz, 380/440 volts, AC supply with spring loaded latch, locking device with a key ribs should be provided inside the door canopy apron and louvers ventilators shall be provided the combined energy meter cum control panel board unit suitable for operation on 3ph, 50 hz, 380/440 volts AC supply shall be consists etc., complete the panel board shall be consist etc., complete the panel board shall be fabricated on single unit in the above componenets panel board for suitable pumpset with star delta staretr out door type 10hp to 15 hp PRED ISSUE RATE								
	Sheshadri Layout	Nos	1	1			1.00	14800.00	14800.00
	Manjunatha Nagara		1	1			1.00	14800.00	14800.00
	Soundarya Layout		1	1			1.00	14800.00	14800.00
11	Fabricating Supplying and mounting MS Box of 16 SWG suitable for floor/ wall mounting fully weather proof with provision for better hear description, 9Providing with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamp with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primes paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 Sq cm (P.No.530, I.No.39, BWSSB SR 2013-14)								
		Sqm Cm	3	1100.00	20.00		66000.00	0.35	23087.00
	Basic Rate	0.33							
	Area Weightage 6%	0.02							
	Total	0.35							
12	Providing & Fixing of Clamps set and Borewell cap to the pump 9MR)								
		No's	3				3.00	1908.00	5724.00
	Basic Rate	1800.00							
	Area Weightage 6%	108.00							
	Total	1908.00							
13	Supplying and fixing 50mm **Non Return Vavle** of vertical type of approved make including cost of all materials labour HOM of equipment with all leads Complete as per Specifcation PWD SR 2018-19. P.No-XLVII. Sl No.16								
	Sheshadri Layout		1	1			1.00	1908.00	1908.00
	Manjunatha Nagara		1	1			1.00	1908.00	1908.00
	Soundarya Layout		1	1			1.00	1908.00	1908.00
	Basic Rate	1800.00							
	Area Weightage 6%	108.00							
	Total	1908.00							

D

Scanned by CamScanner

14	Supplying and fixing 50mm GM Gate Vavle PWD SR 2018-19, P.No-XLVII, Sl No.15								
	Sheshadri Layout	Nos	1	1			1.00	1908.00	1908.00
	Manjunatha Nagara		1	1			1.00	1908.00	1908.00
	Soundarya Layout		1	1			1.00	1908.00	1908.00
	Basic Rate	1800.00							
	Area Weightage 6%	108.00							
	Total	1908.00							
15	Providing & Fixing of 50mm GI Short bend to motor (PWD SR 2018-19, P.No.XXXIX, GI Pipe Fittings, ISI Standard Table								
		No	3	1			3.00	232.14	696.00
	Basic Rate	219.00							
	Area Weightage 6%	13.14							
	Total	232.14							
16	Supplying and fixing 50mm GI Union PWD SR 2015-16, P.No.XXXVII,								
		Nos	3	1			3.00	237.12	711.00
	Basic Rate	223.70							
	Area Weightage 6%	13.42							
	Total	237.12							
17	Supplying and fixing 50mm GI Elbow PWD SR 2015-16, P-XXXVII								
		Nos	3	1			3.00	111.80	335.00
18	Labour charges for laying 1.1 KV class UG cable when supplied by agencies in existing trenches GI pipe / stoneware pipe/ on pole as required, P-427, I-11 (a), BWSSB SR 2012-13.								
		per Length	3	50			150.00	90.64	13596.00
	Basic Rate	88.00							
	Area Weightage 3%	2.64							
	Total	90.64							
19	Erection of combined panel board and meter unit with necessary materials and labour including providing cement concrete foundation bed cont door type etc., complete PRED ISSUE RATE								
		No	3	1			3.00	475.00	1425.00
20	Supplying and fixing miniature Circuit breakers on existing MCB distribution boards using necessary fixing materials and wiring complete as required P-526, I-13 (P, a), BWSSB SR 2013-14.								
		No;s	3	1			3.00	906.40	2719.00
	Basic Rate	880.00							
	Area Weightage 3%	26.40							
	Total	906.40							
21	Supplying and laying of L.T.U.G Cable having aluminium conductor PVC insulated shethed galvanised steel wire/ steel tape armoured cable with PVC outer sheathing 1.1 K V class 4 crore 16 sqmm cable 9Confirming to IS 1554) P.No.553, IT.No 10(d) BWSSB SR 2013-14								
		Mtr	3	45.00			135.00	169.95	22943.00
	Basic Rate	165.00							
	Area Weightage 3%	4.95							
	Total	169.95							
22	Digging of trench of 0.6m deep x 0.5m wide refilling the trench to the required level and consolidating etc., complete P-554, I-12 (b), BWSSB SR2013-14.								
		Mtrs	3	45			135.00	56.65	7648.00
	Basic Rate	55.00							
	Area Weightage 3%	1.65							
	Total	56.65							
23	Supplying and fixing class A GI pipe on pole/Wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class 40mm 9P.No.555, IT No.15 (b) BWSSB SR 2013-14.								

Scanned by CamScanner

		Mtrs	3	3			9.00	249.26	2243.00
	Basic Rate	242.00							
	Area Weightage 3%	7.26							
	Total	249.26							
24	Supplying, fixing, wiring earth electrode for grounding conduits, LC cutouts and other equipments on the meter board using 40mm dia 2.90mm thick GI pipe 2.50m long buried in a pit. The pit should be filled with equal proportion of solt and charcoal 150mm alround the pipe to complete depth. the connection from the pipe to the conduct etc., is to be established through GI wire of size as per ISI specifications 7.3.3 IS 732 using 12mm dia bolts, nuts, washers and check nuts etc., the pipe shall have 16 throught holes of 122mm dia P-552, I-7, BWSSB SR 2013-14.								
		No's	3	1			3.00	1699.50	5099.00
	Basic Rate	1650.00							
	Area Weightage 3%	49.50							
	Total	1699.50							
25	Supply and fixing LT cast iron pot heads suitable for 1.1 KV class 16 sqmm UG cable filled with neccesary bitumen / insulating compound complete with termiinalas, clamps, bolts, nuts, washers etc., P-555, I No-16(b), BWSSB SR 2013-14								
		No's	3				3.00	271.92	816.00
	Basic Rate	264.00							
	Area Weightage 3%	7.92							
	Total	271.92							
26	Supoplying Shunt capacitor's comfirming to IS 2834, 3phase 400/440 volts grade for power factor improvement of roating machinery capacitor in KVAR rating Nos (MR)								
		No's	3				3.00	1350.00	4050.00
27	Providing & Fixing Gun Metal Gate wheel valve confirming to IS Specifivation of approved make as per direction including all lead and lift etc., complete 50mm dia 9P.No.94, It.No.13.796, PWD SR 18-19								
		No's	3	3			9.00	778.04	7002.00
	Basic Rate	734.00							
	Area Weightage 6%	44.04							
	Total	778.04							
28	Supplying and fixing of polished wood board made up not less than 15mm thick plank in both side with plank made out on not more than 2 piecess and fixing the same to wall using tapered inverted wooden plugs screws etc., Size 20x20x2.5 inches (P.No.521, I.No.2(f), BWSSB SR 2013-14								
		No's	3				3.00	311.58	935.00
	Basic Rate	302.50							
	Area Weightage 3%	9.08							
	Total	311.58							
29	Earthwork excavation for foundation of buildings water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. Noll KBS 2.1.C/2.9.4/2.18/2.19 (Pg. No-06, I.No-2.4)PWD - SR 2018-19)								
	Borewell Surrounding Connection	Cum	3	120.00	0.60	0.75	162.00		
	For Repairing existing damaged pipes		3	51.00	0.60	0.75	68.85		
							230.85	475.94	109871.00
	Basic Rate	449.00							
	Add Area Weightage 6%	26.94							
	Total	475.94							

Scanned by CamScanner

30	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement & the cost of cutting chases & making good the same including testing of joints complete. (Concealed work including cutting chases and good the walls etc.)pg no 99,it no.13.87.8.PWD - SR 2018-19)								
	Borewell Surrounding Connection	Rmt	3	120.00			360.00		
	For Repairing existing damaged pipes		3	51.00			153.00		
							513.00	1908.00	978804.00
	Basic Rate	1800.00							
	Add Area Weightage 6%	108.00							
	Total	1908.00							
31	KSRB-2-4: Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5m including cost of all labour complete as specifications.. allow 60% of rate considered under item KSRB 2.3 Page No. 7/ Item No. 2.11/PWD - SR 2018-19)								
	Borewell Surrounding Connection		3	120	0.60	0.75	162.00		
	For Repairing existing damaged		3	70	0.60	0.75	94.50		
	Basic Rate	121.00					256.50	128.26	32899.00
	Add Area Weightage 6%	7.26							
	Total	128.26							
32	KPTCL Deposit Charge								
		Each	3				3.00	12000.00	36000.00
33	Borewell registration charge per Rs 1000 each for BWSSB								
		Each	3				3.00	1000.00	3000.00
								Sub Total	3389262.00
34	Tender Premium Charge 5%								169463.00
35	PMC Charge 1%								33893.00
36	GST Charge 12%								406711.00
37	Miscellaneous and UnforessenCharges								671.00
								Grand Total	4000000.00
	(Rupees Forty Lakhs Only)								

Assistant Engineer
Ward-14

Asst. Exe. Engineer
T.Dasarahalli Sub-Division

Executive Engineer
Dasarahalli Division

ನಂ. EE/DD/AS/116 ದಿನಾಂಕ : 17/01/19
ರೂ. Rs 40.00 Lakhs
Only
ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾತ್ವಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಲಯ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

ನಂ. EE/DD/TS/97/18-19 ದಿನಾಂಕ : 28/01/2019.
ರೂ. Rs: 40:00 Lakhs/-
(Rs. Fourty Lakhs only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ.
ತಾಂತ್ರಿಕ ಸಹಾಯಕರು
ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು.

Scanned by CamScanner